



PLAN 1:750

CUT/FILL SUMMARY		
PROJECT	CUT(m ³)	FILL(m ³)
SPORT COURT BOX EXCAVATION	8,679.05	N/A
SPORT COURT BOX BACKFILL WITH ROCKS	N/A	13,940.29
PROPOSED PARKING LOT	312.65	321.30
PARK FLAT AREA & AREA 2	774.49	10,000±
AREA 1	45.81	2,611.59
PHASE II - NEW TRAIL	15.39	865.45

- NOTES:**
- CONTACT 'B' ONE CALL A MINIMUM THREE WORKING DAYS PRIOR TO START OF CONSTRUCTION.
 - PROVIDE SEDIMENT CONTROL AT THE TOE OF THE EXCAVATED MATERIAL PLACEMENT AREAS.
 - PROVIDE DUST CONTROL ALONG THE ACCESS ROAD AND OTHER AREAS WHEN DIRECTED BY ENGINEER.
- PHASE I - SITE PREPARATION**
- SITE CLEANING AND GRUBBING AS REQUIRED.
 - SPORT COURT BOX EXCAVATION AND EXCAVATED MATERIAL DISPOSED ON SITE.
 - SITE GRADING: PARKING LOT, PARK FLAT AREA & OTHER AREAS.
 - BACKFILL SPORT COURT BOX AREA WITH ROCKS. (TO BE SUPPLIED BY OWNER)
- PHASE I - OTHER CONSTRUCTIONS**
- SPORT COURT BOX CONSTRUCTIONS.
 - WASHROOM.
 - MISC SITE IMPROVEMENTS.
- PHASE II**
- EXISTING TRAIL IMPROVEMENT.
 - ELECTRIC POWER SUPPLY LINE AND WATERMAIN CONSTRUCTION.
 - NEW TRAIL CONSTRUCTION.
 - HYDROSEEDING EXPOSED SOILS AREAS.

- LEGEND:**
- SEWER LINE
 - PROPOSED POWER LINE
 - PROPOSED WATER MAIN
 - EX STORM DITCH
 - EX CULVERT
 - EX STORM COLLECTOR
 - EX TRAIL
 - EX MANHOLE

NO.	DATE	ISSUE
2	19/05/21	FOR DEVELOPMENT PERMIT
1	09/12/20	ISSUED FOR REVIEW



DESIGNED	XX	SURVEYED	XX
DRAWN	CW	START	09/12/20
SCALE HORIZONTAL	AS SHOWN	CHECKED	XX
SCALE VERTICAL	AS SHOWN	APPROVED	XX

Capital Regional District | Parks & Environmental Services

PROJECT REFERENCE: 80.20.03-04 DRAWING NUMBER: 21-R124-01 ISSUE: 1 OF 3